



AUBURN

SAMUEL GINN
COLLEGE OF ENGINEERING

Research Report

**EXPERIMENTAL TESTING AND DESIGN
EVALUATION OF PRECAST THREE SIDED
ARCH BRIDGES**

Submitted to

Foley Products

Prepared by

Justin D. Marshall

J. Brian Anderson

R. Luke Meadows

T. Jared Jensen

JULY 2012

Highway Research Center

Harbert Engineering Center
Auburn, Alabama 36849



www.eng.auburn.edu/research/centers/hrc.html

DISCLAIMERS

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of Auburn University or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

NOT INTENDED FOR CONSTRUCTION, BIDDING, OR PERMIT PURPOSES

Justin D. Marshall, Ph.D., P.E.

J. Brian Anderson, Ph.D., P.E.

Research Supervisors

ABSTRACT

The use of precast, three-sided arch culverts has become fairly popular for new short-span bridges and bridge replacements due to their rapid construction time, aesthetic appeal, and minimal impact to the waterway, but little research has been performed into the strength of these structures. It has been thought that, due to arching action, large lateral earth pressures can be developed in the backfill behind the legs, and that these pressures allow the bridge to achieve strengths much larger than possible without the confinement of the backfill soil. The research detailed in this report sought verify the behavior of this bridge system through field testing of an existing bridge, as well as two ultimate load tests on individual bridge units. Nonlinear numerical models of the bridge sections were calibrated with the results from the laboratory experimental tests and used to evaluate the design procedure and safety of the arch bridge sections.

It was concluded that the test bridges were too stiff to cause enough lateral deflection to mobilize passive earth pressures in the backfill, and the earth pressures had a minimal effect. The bridges reached the expected strength although some issues with bridge performance were discovered at ultimate loads. Although there were some discrepancies between the design structural model and the calibrated structural model, the design methodology produced a safe design with reasonable conservatism.

TABLE OF CONTENTS

LIST OF TABLES	v
LIST OF FIGURES	vi
CHAPTER 1: INTRODUCTION	1
1.1 Overview	1
1.2 Project Purpose and Scope	1
CHAPTER 2: FIELD TEST OF 42 FT SPAN ARCH	2
2.1 Introduction	2
2.2 Instrumentation	2
2.3 Testing Procedure	4
2.4 Analysis, Results and Discussion of Testing	6
2.5 Chapter Summary	9
CHAPTER 3: LABORATORY TEST OF 20 FT SPAN ARCH.....	10
3.1 Introduction.....	10
3.2 Instrumentation	12
3.3 Testing Setup and Equipment	13
3.4 Testing Procedure	15
3.5 Analysis, Results and Discussion of Testing	15
3.6 Observed Bridge Behavior and Failure	18
3.7 Chapter Summary	22
CHAPTER 4: LABORATORY TEST OF 36 FT SPAN ARCH	23
4.1 Introduction	23
4.2 Instrumentation and Setup	26
4.3 Testing Procedure	27
4.4 Analysis Results and Discussion of Testing	27
4.5 Observed Bridge Behavior and Failure	31
4.6 Chapter Summary	35
CHAPTER 5: COMPUTER MODELING	36
5.1 Introduction	36
5.2 Model Development	36
5.3 Nonlinear Analysis	37

5.4 Model Analysis Results	39
5.5 Chapter Summary	44
CHAPTER 6: DESIGN METHODOLOGY	45
6.1 Introduction	45
6.2 Modeling and Analysis	45
6.3 Experimental Results Versus Design	51
6.4 Chapter Summary	52
CHAPTER 7: SUMMARY, CONCLUSIONS AND RECOMMENDATIONS	53
7.1 Summary	53
7.2 Conclusions	53
7.3 Recommendations	54
REFERENCES	56

LIST OF TABLES

Table 3-1	20 ft Bridge Unit Reinforcement Details (Foley Arch, 2010)	10
Table 4-1	36 ft Bridge Unit Reinforcement Details (Foley Arch, 2011)	23
Table 6-1	Design Calculation Properties	48
Table 6-2	Comparison of RISA and SAP2000 Model Moments	50
Table 6-3	Test Structure Midspan Properties	51
Table 6-4	Ratio of Design to Test/Model Specimen Properties	51

LIST OF FIGURES

Figure 2-1	42 ft Bridge Structure	2
Figure 2-2	42 ft Bridge Unit Overall Dimensions (Foley Arch, 2010)	3
Figure 2-3	Field Test Strain Gage Layout	4
Figure 2-4	Earth Pressure Cell Layout	4
Figure 2-5	Bridge Unit Layout	5
Figure 2-6	Live Load Testing	6
Figure 2-7	Cross Section Layout	6
Figure 2-8	Moments due to Live Load Only Versus Time	7
Figure 2-9	Live Load Moment Versus Rear Axle Location – Run 1	8
Figure 2-10	Lateral Earth Pressure due to Live Load Only Versus Time	9
Figure 2-11	Live Load Lateral Earth Pressure Versus Rear Axle Location – Run 1	9
Figure 3-1	20 ft Bridge Unit Reinforcement Layout (Foley Arch, 2010)	11
Figure 3-2	20 ft Cross Section Layout	12
Figure 3-3	20 ft Wirepot and Load Cell Layout	13
Figure 3-4	Actuator Loading Frames	13
Figure 3-5	Bridge Base Plate	14
Figure 3-6	Strain-Gaged Rods to Apply Additional Vertical Load	14
Figure 3-7	Moment Versus Total Load – Second Ultimate Load Test	16
Figure 3-8	Load Cell Reaction Versus Total Load – Second Ultimate Load Test	17
Figure 3-9	Deflection Versus Total Load – Second Ultimate Load Test	18
Figure 3-10	Corner Crack at 156 kip Total Load	19
Figure 3-11	Corner Crack at 175 kip Total Load	20
Figure 3-12	Corner Crack Immediately Prior to Failure	20
Figure 3-13	Failure Mechanism	21
Figure 3-14	Failure Load Configuration	21
Figure 3-15	Failed Bridge Section	22
Figure 4-1	36 ft Bridge Unit Overall Dimensions (Foley Arch, 2011)	24
Figure 4-2	36 ft Bridge Unit Reinforcement Layout (Foley Arch, 2011)	25
Figure 4-3	36 ft Cross Section Locations	26
Figure 4-4	36 ft Wirepot and Load Cell Layout	27
Figure 4-5	Steel Reinforcement Testing Results	28
Figure 4-6	Moment Versus Load	29
Figure 4-7	Load Cell Reaction Versus Load	30

Figure 4-8	Deflection Versus Load	31
Figure 4-9	Initial Spalling on Bridge Leg	32
Figure 4-10	Midspan Cracking – 120 kips Total Load	32
Figure 4-11	Bridge Cracking Immediately Prior to Failure	33
Figure 4-12	Bridge Section Immediately After Failure	33
Figure 4-13	Failure Load Configuration	34
Figure 4-14	Failure Through Lifter Location	35
Figure 5-1	20 ft Clear Span – SAP2000 Elements	37
Figure 5-2	36 ft Clear Span – SAP2000 Elements	37
Figure 5-3	Hinge Locations and Labels – 20 ft Clear Span Model	38
Figure 5-4	Hinge Locations and Lables – 36 ft Clear Span Model	39
Figure 5-5	Model Versus Laboratory Specimen – 20 ft Span Midspan Moment	40
Figure 5-6	Model Versus Laboratory Specimen – 20 ft Span Midspan Displacement	41
Figure 5-7	Model Versus Laboratory Specimen – 20 ft Span Corner Displacement	41
Figure 5-8	Model Versus Laboratory Specimen – 36 ft Span Midspan Moment	42
Figure 5-9	Model Versus Laboratory Specimen – 36 ft Span Midspan Displacement	43
Figure 5-10	Model Versus Laboratory Specimen – 36 ft Span Corner Moment	43
Figure 6-1	Extruded View – 20 ft Span RISA Model	46
Figure 6-2	Moment Diagram – 20ft Span RISA Model	46
Figure 6-3	Beam Elements – 36 ft Span RISA Model	47
Figure 6-4	Moment Diagram – 36 ft Span RISA Model	47
Figure 6-5	Moment Diagram of Factored Design Loads – 20 ft SAP2000 Model	49
Figure 6-6	Moment Diagram of Factored Design Loads – 36 ft SAP2000 Model	49

Chapter 1

INTRODUCTION

1.1 Overview

The use of precast, three-sided arch culverts has become fairly popular for new bridges and bridge replacements, due to their rapid construction time, aesthetic appeal, and minimal impact to the waterway. However, little research has been performed into the strength of these structures. Foley Products contracted with Auburn University to investigate and demonstrate the strength of arches that are currently produced and used for bridge applications.

1.2 Project Purpose and Scope

The objective of the project was to validate the strength and design methodology of the Foley Arch bottomless bridge. Three experimental tests including a serviceability field test of a 42 ft clear span and laboratory ultimate strength tests of 20 ft and 36 ft clear span sections were completed. Data from the laboratory tests was used to develop analytical computer models. The models were developed to the point that the analytical results were correlated to the results of the laboratory test. The tests and structural computer models could then be used to validate the design methodology used for the arches. This report presents the data from the three tests and the analysis of the data and the design methodology used for the Foley Arch. This report represents an abbreviated summary of the research. More detail on the research project can be found in Meadows (2012) and Jensen (2012).

Chapter 2

FIELD TEST OF 42 FT SPAN ARCH

2.1 Introduction

A 42 ft span bridge constructed in Midland, North Carolina was used for a field test of the Foley precast arch culvert bridge system. The bridge consisted of 13 units placed side-by-side, spanning over Wiley Branch Creek on Cabarrus Station Road. Each unit was 42 ft long clear span, four feet wide, and has a 14ft inside clear height at midspan. An image of the bridge structure prior to placement of backfill can be seen in Figure 2-1. Backfill was placed and compacted along the sides and top of the bridge up to a total of approximately two feet of cover over the midspan prior to live load testing. Figure 2-2 is an image of unit overall dimensions taken from the design drawings.



Figure 2-1 42 ft Bridge Structure

2.2 Instrumentation

In order to measure moments and axial forces within the bridge units, five vibrating wire strain gages were placed along the inside centerline of three identical bridge units, with one highly-instrumented unit also having corresponding vibrating wire strain gages on the outside surface. The strain gage layout and gage numbering scheme is detailed in Figure 2-3. On the first two units, one gage is placed on each of the legs at the points shown on the interior. On the highly-instrumented unit, the inner gage layout is the same with the exception that one of the gages placed at the beginning of the standard arch curvature had to be offset from the centerline by one foot due to the presence of rebar chairs. The gages on the outer layer on this unit were placed at the same cross-sections and on the centerline in order to find the strains at the same points on

opposite sides of the cross section. The only exception to this was at the aforementioned offset location, in which two gages, one at the corresponding offset and one on the centerline, were used on the outside of the unit.




Figure 2-2 42 ft Bridge Unit Overall Dimensions (FoleyArch, 2010a)




Figure 2-3 Field Test Strain Gage Layout

In addition, two earth pressure cells (EPCs) were placed on each exterior leg of the highly-instrumented unit, one near the bottom and one near the top. The exact layout of each EPC, numbered 38 through 41, can be seen in Figure 2-4. The reason the EPC 39 is not as low as EPC 41 is due to the presence of some backfill on that side when the pressure cells were installed.




Figure 2-4 Earth Pressure Cell Layout

The three instrumented units were placed next to each other in order to better determine how a vehicle load is spread through the backfill to the actual bridge units. The highly-instrumented unit was placed furthest to the outside in order to maximize the effect of the live load in that unit. This occurs because, when the live load is directly above it, there is less width of the bridge for the live load to be distributed over. Figure 2-5 shows the layout of the three gaged units in the 13 unit bridge.

2.3 Testing Procedure

This section consists of the procedure used during testing. For this test, two sets of data were recorded. The first set was recorded during the backfill process to measure construction loads on the bridge. The second set was recorded during a live load test on the bridge after backfilling.

On September 7, 2010, after the bridge units had been placed and grouted into the footings, the strain gages and earth pressure cells were installed. Data was recorded with these instruments over the next 12 days. During this time, backfill was placed around the legs and over the top of the bridge using standard construction practices up to a total cover of two feet. This

data was recorded to see if the stresses on the structure during construction were more critical than those experienced during service.




Figure 2-5 Bridge Unit Layout

On September 19, 2010, a live load test using a full dump truck was performed. The strategy was to have the truck, which had a gross vehicle weight of 56,820 lbs, drive over the bridge, stopping at set intervals long enough for the data acquisition system to take several measurements, and then proceeding along the bridge. At each stop, the location of either the front axle or the centerline of the two rear axles was measured. The truck made a total of three passes over the bridge, two heading toward the northeastern side and one heading toward the southwestern side. For the first and third run, traveling toward the northeastern side, the truck was aligned along the roadway such that the outside wheels ran over the highly-instrumented unit. For the second run, traveling toward the southwestern side, the truck was aligned such that the outside wheels were four feet over from the highly-instrumented unit. Figure 2-6 shows an image of the live load testing.



Figure 2-6 Live Load Testing

2.4 Analysis, Results, and Discussion of Testing

This section contains the measured data as well as calculated results from the 42 ft bridge test. For analysis purposes, the bridge units were divided into five instrumented cross sections based on the strain gage layout. Two cross sections were on the legs, two were near the corners, and one was at midspan. An image of this cross section layout is in Figure 2-7.




Figure 2-7 Cross Section Layout

Cylinder tests of the concrete in the bridge revealed the highly instrumented unit had a compressive strength, f'_c , of 8,670 psi. The other typical units had compressive strengths of 6,150 psi and 6,940 psi. These tests were performed by Foley Products prior to shipping of the units, in order to confirm adequate strength gain as part of their quality control.

Calculations of moment and axial force in the cross sections were done assuming a linear elastic, homogeneous, rectangular cross section. Using the strains from the two strain gages on either side of the cross section a linear strain profile was established. The strain profile was then converted into a stress profile using the modulus of elasticity of the concrete. The stress profile

was then turned into axial forces and moments using the cross sectional properties of the concrete. Moments were based on the linear elastic behavior stress.

The magnitude of moments measured in the bridge units was as expected. Larger, positive moments were measured at midspan, while smaller, negative moments were measured at the corners and legs. Moments were calculated on a per foot width of bridge, as was done in design. The maximum moment developed by the truck load was 10.5 kip-ft/ft at midspan when the rear axles were centered over midspan. This compares favorably to the factored ultimate midspan moment strength of 38 kip-ft/ft. As for the other cross sections, their maximum moments occurred when the rear axles were centered seven to ten feet away from midspan. The maximum moment due to the truck load was -6.5 kip-ft/ft for the corner gages and -5 kip-ft/ft for the leg. It is of note to point out that the strains did not go above the theoretical concrete cracking strain of $131 \mu\epsilon$, either during the backfill operation or during live load testing.

Figure 2-8 shows the development of moment versus time in the highly-instrumented unit, where the effect of the truck load was most pronounced. Figure 2-9 shows the development of moment versus the position of the centerline between the two rear axles for the first run.




Figure 2-8 Moments due to Live Load Only Versus Time




Figure 2-9 Live Load Moment Versus Rear Axle Location - Run 1

Moment diagrams showed that for all measured cross sections, the maximum moment occurred when the centerline of the two rear axles was over or near midspan. Negative moments in the legs and corners were not as large as the positive moment. The negative moments were largest when the rear axle was near the quarter span.

Axial forces in the cross sections were found to be negligible. However, it is worth noting that the presence of backfill around and above the bridge put all cross sections into a net compression, which helped prevent the concrete from cracking.

Lateral earth pressures on the external walls developed as anticipated when the truck load was applied to the bridge. As the truck load thrust the arch outward, larger lateral earth pressures were measured at the top of the wall, while very small pressures were measured at the bottom of the wall, indicating a “pinned” support condition, as opposed to a “roller” support condition. Figure 2-10 shows how the earth pressures developed versus time during the live load test in each EPC. Figure 2-11 shows the development of earth pressures versus the position of the centerline between the two rear axles for each of the three test runs. This graph provides a better illustration of the effect of the truck load as it passes over the bridge.

Lateral earth pressures that developed during the live load testing indicate that the largest pressures are felt at the top of the wall, with very small or even no lateral earth pressure developing near the bottom of the wall. This means that the grouted bottom of the bridge behaved as a pin, with backfill acting as a distributed spring resistance to the lateral displacement of the bridge. The largest measured earth pressures also occurred when the centerline of the two rear axles was over midspan.




Figure 2-10 Lateral Earth Pressure due to Live Load Only Versus Time




Figure 2-11 Live Load Lateral Earth Pressure Versus Rear Axle Location - Run 1

2.5 Chapter Summary

The 42 ft bridge behaved exceptionally well and was very stiff. Measurements taken during the backfill operation indicated that no cracking occurred during construction, and that the presence of backfill creates a net compression in the bridge. Under a live load test using a truck weighing 56,820lbs, the bridge showed no signs of cracking. Measured moment magnitudes were within reason, and relatively small lateral earth pressures were recorded. Pinned support behavior at the keyed footings was verified by the negligible mobilization of lateral earth pressures near the bottom of the bridge.

Chapter 3

LABORATORY TEST OF 20 FT SPAN ARCH

3.1 Introduction

This chapter details the test program and results for the 20 ft span bridge section. A 20 ft span bridge unit was used for a laboratory test of the Foley Arch precast arch culvert bridge system. The single unit of a multi-unit bridge was designed for ten feet of backfill plus live load. The unit had a 20 ft clear span, an inside clear height of eight feet at midspan, and was four feet wide. Figure 3-1 shows the overall dimensions and the reinforcement layout in the unit, with the exact reinforcement used detailed in Table 3-1.

The bridge unit was cast on March 2, 2011 at the Foley plant in Winder, GA, and shipped to the Structures Research Laboratory at Auburn University on June 1, 2011. Three load tests were performed on the bridge between August 3 and August 10, 2011. The bridge section ultimate strength was approximately 182 kips.

Table 3-1 20 ft Bridge Unit Reinforcement Details (FoleyArch, 2010b)

Designation:	Mesh Size	Length (ft)	Transverse Area Supplied (in ² /ft)	Longitudinal Area Supplied (in ² /ft)
A1A	D16.7xD8 2x4.75	16'-6"	1.002	0.202
A1B	D16.7xD8 2x4.75	14'-0"	1.002	0.202
A2	D10.5xD8 4x7	11'-2"	0.315	0.137
A3	D10.5xD8 2x7	15'-0"	0.63	0.137
A4	D10.5xD8 4x4	10'-9"	0.315	0.24
Design based on uncoated reinforcing meeting ASTM A-615, Grade 60, $f_y = 60,000$ psi				
Minimum Yield Strength for welded wire fabric shall be 65,000 psi				




Figure 3-1 20 ft Bridge Unit Reinforcement Layout (Foley Arch, 2010b)

3.2 Instrumentation

The 20 ft clear span bridge unit was initially instrumented with 15 sister bar strain gages, ten concrete surface strain gages, three displacement potentiometers, or wirepots, and four load cells. Two additional wirepots were added following the preliminary testing.

Strain gages were placed at five cross sections on the bridge: at midspan, at the corners where the section began to increase in depth, and on the legs where the section began to increase in thickness. The layout of the instrumented cross sections is shown in Figure 3-2. Three sister bar gages were placed at each location and tied to the reinforcing cage. These sister bar gages were tied on the side of the cross section that would be the expected tension side, meaning the inner side of the bridge at midspan, and the outer side of the bridge at the corners and legs. Two concrete surface strain gages were placed at each cross section, at third points along the width, on the concrete surface expected to be in compression, meaning the outer side at midspan, and the inner side at the corners and legs.




Figure 3-2 20 ft Cross Section Layout

The first three wirepots were placed in positions to measure the maximum deflections. Therefore, one was placed at midspan to measure vertical deflection, and the other two were placed at the top of the walls to measure lateral deflection. After initial testing, it was observed that the maximum lateral deflections occurred within the wall, and not at the top. So for the final test, a fourth and fifth wirepot were placed horizontally at a point 48 in above the bottom of the bridge, near cross sections one and five.

In addition, four load cells were used to measure the horizontal reaction at the base of the bridge. At the base of each leg, two load cells were used to restrain the lateral movement of the leg. This was done to effectively create a pinned support condition, like that experienced in the field. A sketch of the wirepot and load cell layout can be seen in Figure 3-3.




Figure 3-3 20 ft Wirepot and Load Cell Layout

3.3 Testing Setup and Equipment

This section contains some details on testing setup outside of instrumentation. It includes details on the various loading frames used for testing, the actuators used to apply the load, and the data acquisition system.

The load frame designed for this project consisted of three actuators pulling down on the bridge unit from underneath. The frames with the three actuators can be seen in Figure 3-4. The actuators were each tied to a beam which then framed up to another beam, which was bearing on the top of the bridge. Based on the layout of anchor points in the strong floor, the three actuators were spaced at four foot intervals, with the middle actuator located at midspan of the bridge unit.



Figure 3-4 Actuator Loading Frames

Initial tests also used a system of instrumented, horizontal threaded rods, one of which can be seen in Figure 3-4, which were used to approximate the effects of lateral soil pressure. These were only attached during service level testing to look at the effect of the restraint on

development of moments. The effect of the lateral restraint was minimal so it is not detailed in this report. More information can be found in (Meadows, 2012).

The base plates, seen in Figure 3-5, provided both the vertical and horizontal reaction forces. The horizontal restraint of the bottom of the leg was provided to simulate field conditions, in which the bridge units are placed into keyed footings.

For the second ultimate load test, additional vertical load was needed to fail the bridge unit. This was supplied by spanning two angles across the bridge on either side of the midspan actuator. These angles were then tied to the floor using the threaded rods used previously for the lateral resistance system. The gaged threaded rods were used to calculate the additional load being applied to the bridge. Load was applied by tightening the bolts holding the assembly together. This additional loading frame is shown in Figure 3-6.



Figure 3-5 Bridge Base Plate




Figure 3-6 Strain-Gaged Rods Used to Apply Additional Vertical Load

3.4 Testing Procedure

This section consists of the procedure used during testing. For this bridge unit, three separate tests were performed. The first test was a service level test using the lateral resistance frame. The second test was an ultimate strength test without the lateral resistance frame. After being unable to achieve the ultimate load, a third test was needed. The third test was another ultimate strength test using additional vertical loading. The second ultimate test provided the greatest amount of information on performance of the bridge, so it will be the only test presented in this report. More details on the service level and first ultimate test can be found in (Meadows, 2012). The service level test demonstrated that the horizontal restraint has little effect on the service level performance of the bridge section. The first ultimate test demonstrated that the initial estimates of strength were too low as the three actuators reached capacity without failing the bridge.

On August 10, 2011, the second ultimate level load test was performed. This test was performed using the actuators as well as the additional vertical loading frame consisting of angles and instrumented threaded rods. Two additional displacement wirepots were added at a height of 48 in on the side walls of the bridge unit in order to measure the horizontal displacement. Load was applied by pulling down on the actuators, followed by tightening the threaded rods. Eventually, the bridge failed at an approximate total load of 182 kips.

3.5 Analysis, Results, and Discussion of Testing

This section contains the measured data as well as calculated results from the 20 ft bridge test. For analysis purposes, the bridge is divided into five instrumented cross sections based on the strain gage layout. Two cross sections are on the legs, two are near the corners, and one is at midspan. The cross sections are the same as those in Figure 3-3.

Cylinder tests revealed the concrete to have a compressive strength, f'_c , of 12,500 psi. Modulus of elasticity tests show the concrete to have a modulus, E_c , of 5,950 ksi. This compressive strength value is quite high. Typical 28-day compressive strength values are 6,000 psi to 7,000 psi. The high compressive strength value is a function of the fast setting concrete used for this precast unit.

Strains at the same location within each cross section were approximately equal, meaning sister bar strain gages agreed with each other and with concrete surface strain gages. This observation indicated two very important things. First, load testing did not cause any torque in the bridge. Second, the strain gages were functioning properly. In addition to the two sister bar strain gages that were faulty after casting of the bridge, two other gages malfunctioned during the course of the three tests. In such cases, those particular strain gages were neglected. At all cross sections, at least one sister bar strain gage measured properly.

Very small strains were measured at the corner cross sections, locations two and four. In some cases these cross sections measured strains opposite the anticipated sign, for example, concrete gages in tension. It was determined that the location of these gages was further out on the arch than intended, near the inflection points rather than at the points of maximum negative moment.

Using the strains measured on the concrete compressive surface and within the cross section near the steel, moments and axial forces were calculated. More detail on the calculation of moments and axial forces can be found in Meadows (2012) as these assumptions and methods are beyond the scope of this abbreviated report.

It was found that cross sections two and four were placed near the inflection point. They therefore experienced relatively low strains and curvature opposite of what was expected. For these sections, an analysis similar to what was used on the 42 ft field test was used.

Moments in the five cross sections during the second ultimate load test are shown in Figure 3-7. Note that the sign associated with the moment is relative to the position of the concrete and sister bar strain gages. Therefore a positive sign means that the moment is such that tension is in the sister bars and compression is in the concrete surface gages. The axial forces determined from the tests were much higher than expected and were also very sensitive to assumptions made during the analysis. Even though the forces were calculated to be much higher than expected the magnitude of the forces did not affect performance and are not reported.




Figure 3-7 Moment Versus Total Load - Second Ultimate Load Test

Load cell reactions at the base of the bridge legs during the second ultimate load test are shown in Figure 3-8. The forces in the load cells are small compared to the total load on the bridge. This is due to the horizontal friction force between the baseplate and the bridge. In addition to providing the vertical support of the legs, the bearing surface of the concrete bridge on

the steel baseplate resists the bridge legs sliding outward through friction. Therefore, a smaller portion of the horizontal reaction goes into the load cells.




Figure 3-8 Load Cell Reaction - Second Ultimate Load Test

Figure 3-9 shows individual wirepot displacements during the second ultimate load test. Larger displacements at midheight of the legs, compared to displacements at the top of the legs, indicated that the legs were flexible compared to the axial stiffness of the arch. The long legs, which contain less reinforcement than the arch, bowed significantly. Care should be taken to design the leg dimensions and reinforcement to ensure that unit behavior is controlled by the behavior of the arch itself.

In all three tests, deflections increase at an approximately linear rate, and there is very little flattening of the curve prior to failure in the final test. A vertical deflection of 2.10 in was measured at failure. This ultimate load deflection translates to roughly $L/120$. In addition, the unrestrained lateral deflections of the bridge walls were relatively small, the maximum being 1.04 in at wirepot five. Due to these small deflections, passive pressure in the backfill soil would not mobilize, but the soil would most likely remain in an at rest pressure condition. Therefore, for the smaller, stiffer 20 ft span, backfill soil would not significantly increase the ultimate strength of the bridge.




Figure 3-9 Deflection Versus Total Load - Second Ultimate Load Test

3.6 Observed Bridge Behavior and Failure

Initial cracking was observed around 48 kips total load, with many thin cracks opening in the high moment areas. The initial cracking took place during the service load test was distributed in all the high moment regions of the bridge section. However, these flexural cracks did not significantly propagate or widen throughout testing, because the bridge redistributed the load to the uncracked concrete. Furthermore, the lack of crack widening indicates that the reinforcement did not yield. More hairline cracks appeared as testing progressed, but crack sizes did not become significant until near ultimate loading.

The first significant crack occurred at a total load of 120 kips. This crack ran straight through the corner of the bridge at its thickest point. The crack continued through the corner, beginning to run down the leg with the reinforcement. Figure 3-10 is an image of the crack propagating and widening at a total load of 156 kips. A similar crack opened up in the opposite corner as well.



Figure 3-10 Corner Crack at 156 kips Total Load

The critical shear crack that would eventually be the failure mechanism did not appear until approximately 175 kips of total load. This crack was a shear crack running through the arch close to the corner of the bridge. Figures 3-11 – 3-13 show the crack forming, widening immediately prior to failure, and the failure mechanism.




Figure 3-11 Corner Crack at 175 kip Total Load



Figure 3-12 Corner Crack Immediately Prior to Failure



Figure 3-13 Failure Mechanism

The 20 ft span failed under a total applied load of 182.1 kips. The failure mechanism was a shear crack near the corner on the arch itself. The shear crack opened up on the side of the bridge containing cross sections four and five, wirepots three and five, and load cells three and four. The load configuration is shown in Figure 3-14. A picture of the failed structure is shown in Figure 3-15.




Figure 3-14 Failure Load Configuration

The shear failure mechanism of the bridge was unexpected. A general flexural failure caused by flexural hinges forming near the corners and at midspan was considered more likely. However, due to the stiffness of the concrete and large amounts of reinforcement steel, especially at midspan, steel did not significantly yield, causing a different failure mechanism.

The failure mechanism was not ductile and developed quickly. The bridge failed rapidly and could not carry its own dead weight after failure. While flexural cracks did develop in the walls, corners, and midspan of the bridge, none of them opened up very much after forming, due to the bridge redistributing the load to stiffer sections. Overall, the flexural stiffness of this shorter span bridge forced the bridge to be controlled by shear strength of the concrete. The relatively thin section, containing no shear reinforcement, was not large enough to resist the large shear forces developed during the test.



Figure 3-15 Failed Bridge Section

3.7 Chapter Summary

The 20 ft bridge unit appeared to have sufficient strength, but did not fail with a ductile mechanism. While flexural cracking did occur in the high moment areas at early loading stages, these cracks did not significantly widen or propagate during testing, due to the bridge unit redistributing load around the cracks and the reinforcement not yielding. The bridge unit held 182.1 kips of force before failure. Immediately prior to failure, maximum deflections were 2.1 in downward at midspan, and 1.04 in laterally in the walls. The failure mechanism was a shear failure of the concrete, with a shear crack running through the arch section near the corner.

Chapter 4

LABORATORY TEST OF 36 FT SPAN

4.1 Introduction

A 36 ft span bridge unit was used for a laboratory test of the Foley Arch precast arch culvert bridge system. The single unit of a multi-unit bridge was designed for five feet of backfill plus live load. The unit has a 36 ft clear span, an inside clear height of nine feet at midspan, and is four feet wide. An image of the unit overall dimensions taken from the design drawings can be seen in Figure 4-1. An image of the reinforcement layout in half of the unit can be seen in Figure 4-2, with the exact reinforcement used detailed in Table 4-1. The reinforcement layout in the two halves of the unit was symmetric about midspan.

Table 4-1 36 ft Bridge Unit Reinforcement Details (Foley Arch, 2011)

Designation:	Mesh Size	Length (ft)	Transverse Area Supplied (in ² /ft)	Longitudinal Area Supplied (in ² /ft)
A1A	D10xD10 2x3.8	24'-0"	0.6	0.315
A1B	D13.2xD5.5 2x16	30'-0"	0.792	0.041
A2	D5.5xD10 2x8	9'-9"	0.33	0.15
A3A	D10xD10 2x8	16'-1"	0.6	0.15
A3B	D10xD5.5 2x16	13'-1"	0.6	0.041
A4	D5.5xD10 2x3.8	26'-0"	0.33	0.315
A5	D5.5xD10 2x8	7'-10"	0.33	0.15
Design based on uncoated reinforcing meeting ASTM A-615, Grade 60, $f_y = 60,000$ psi				
Minimum Yield Strength for welded wire fabric shall be 65,000 psi				






Figure 4-2 36 ft Bridge Unit Reinforcement Layout (FoleyArch, 2011)

The bridge unit was cast on December 1, 2011 at the Foley plant in Winder, GA, and shipped to Auburn University on December 14, 2011. The unit was shipped on its side and brought to Scott Bridge Company of Opelika, AL, where it was taken off the truck with a crane, rotated to an upright position, and placed back on the truck with the forward most leg on rollers. The unit was then brought to the Structures Research Laboratory at Auburn University. The weight of the unit was more than the laboratory crane's capacity, so positioning the bridge was done by placing one

end on rollers, lifting up the other end, and using the forklift to push or pull the bridge into place. This process caused some minor cracking in the unit, as well as some slight misalignment of the legs. A single load test was performed on the bridge on January 6, 2012. At ultimate load conditions, the unit held more than 151 kips before failing.

This chapter details how the 36 ft unit was tested, as well as the results. It contains sections on the instrumentation, setup, and procedure used for testing. It also contains analysis and results from testing, followed by discussion of those results.

4.2 Instrumentation and Setup

The 36 ft clear span bridge unit was instrumented with 15 sister bar strain gages, ten concrete surface strain gages, three displacement potentiometers, or wirepots, and four load cells. Strain gages were placed at seven cross section locations on the bridge: at midspan, at the corners where the arch section began to increase in thickness, within the thicker corner sections, and on the legs where the section began to increase in thickness. The layout of the instrumented cross sections can be seen in Figure 4-3. Two sister bar gages were placed at each location and tied to the reinforcing cage. Three sister bar gages were used at midspan. These sister bar gages were tied on the side of the cross section that would be the expected tension side, meaning the inner side of the bridge at midspan, and the outer side of the bridge at the corners and legs. Two concrete surface strain gages were placed at each cross section, at third points along the width, on the concrete surface expected to be in compression, meaning the outer side at midspan, and the inner side at the corners and legs.




Figure 4-3 36 ft Cross Section Locations

The three wirepots were placed in positions to measure the maximum deflections that the bridge experienced. Therefore, one was placed vertically at midspan to measure vertical deflection, and the other two were placed horizontally at the top of the walls to measure lateral deflection.

In addition, four load cells were used to measure the horizontal reaction at the base of the bridge. Two load cells were placed on the exterior side of each leg, bearing against the leg to

provide lateral restraint. This was done to effectively create a pinned support condition, like that experienced in the field. An image of the wirepot and load cell layout can be seen in Figure 4-4.




Figure 4-4 36 ft Wirepot and Load Cell Layout

The load frame used for testing the 36 ft bridge unit is the same frame used during the 20 ft bridge unit test. Once again, the three actuators were spaced at four feet, with the middle actuator at midspan.

4.3 Testing Procedure

In order to better understand the stress-strain behavior of the reinforcement used for this bridge unit, seven bars taken from steel reinforcement samples were tested in a tension testing machine. Four of the bars were cut from extra mats prior to casting. These bars are the same size, D10 bars, as the bars used as primary negative moment reinforcement in the legs and the corners. The remaining three bars were cut directly from the bridge unit during demolition after testing was completed. These larger D13.2 bars were cut from the primary positive moment reinforcement used at midspan.

On January 6, 2012, an ultimate level load test was performed on the 36 ft bridge section. The load was applied slowly and evenly in the same manner as the previous tests. Near the end of the actuators' capacity, the bridge failed when a hinge formed near the corner within the arch, in between the two gage locations in that corner.

4.4 Analysis, Results, and Discussion of Testing

This section contains the measured data as well as calculated results from the 36 ft bridge test. For analysis purposes, the bridge is divided into seven instrumented cross sections based on the strain gage layout. Two cross sections are on the legs, two are near the corners where it is thicker, two are near the corners where the thinner arch begins, and one is at midspan. The cross sections are the same as those in Figure 4-4.

Cylinder tests revealed the concrete to have a compressive strength, f'_c , of 7,040 psi. Modulus of elasticity tests show the concrete to have a modulus, E_c , of 4,100 ksi. This compressive strength value is fairly typical of precast, three-sided arch units, which have a typical 28 day compressive strength of 6,000 psi to 7,000 psi.

It was found that reinforcement had both sufficient strength as well as ductility. A graph showing the full stress-strain curves for each of the seven steel samples can be seen in Figure 4-5. Data showed that the modulus of elasticity was approximately 26,500 ksi, however, which is unusual for steel. Data showed that the steel stress-strain curve increases linearly before beginning to flatten out at a yield plateau. Specimens did not exhibit strain hardening, increasing strength after yielding, but instead continued to deform with very little strength increase prior to fracture. In addition to the smaller modulus of elasticity, one other anomaly was noted. It was found that yielding of the smaller D10 bars was around 70 ksi, while the larger D13.2 bars did not yield until roughly 90 ksi, which is very high for this steel. However, due to the range of strains measured during testing, this anomaly did not prove to be significant.




Figure 4-5 Steel Reinforcement Testing Results

Strains measured at the same cross section location were close to each other, which indicated two things. First, load testing did not cause any torque in the bridge. Second, the strain gages were measuring strains properly. Other than the one sister bar strain gage that was faulty after casting, no other strain gages became faulty during the course of the test.

The highest strains were measured in cross sections three, four, and five, as expected. Steel strains in all three of these cross sections were high enough to cause yielding, with the maximum strains being around 0.0035, which occurred in cross section five right before failure. Steel strains in cross sections one, two, six, and seven did not reach yielding.

Moments and axial forces were calculated in the same way as described previously. The primary differences were that the concrete rupture stress, f_r , is 630 psi, and all cross sections were analyzed using cracked section analysis. Another notable difference was that the test data developed from the steel specimens was used to determine the stresses in the steel.

Moments in the seven cross sections during the ultimate load test are shown in Figure 4-6. Moments in cross sections two and six are the highest due to the thicker, stiffer cross section within the corner of the bridge. Note that the sign associated with the moment is relative to the position of the concrete and sister bar strain gages. Therefore a positive sign means that the moment is such that tension is in the sister bars and compression is in the concrete surface gages. Also note that, due to the preliminary loading portion of the test, there are loading, unloading, and reloading portions of the graph. The unloading curve for each cross section does not return to zero, indicating that there is permanent strain deformation, which is expected. After load is removed, the fictitious moment caused by the permanent strain is subtracted out before beginning the reloading portion of the graph.




Figure 4-6 Moment Versus Load

As with the 20 ft span, calculated axial forces were determined to be far beyond theoretical values. It was found that the axial force calculation is extremely sensitive to even minor changes in measured strain. These large forces, however, do not significantly affect the flexural strength of the cross section, due to the large cross sectional area of the four foot wide bridge unit. Load cell reactions at the base of the bridge legs during the ultimate load test are presented in Figure 4-7. Note that, due to the preliminary loading portion of the test, there are loading, unloading, and reloading portions of the graph. The unloading curve for each load cell does not return to zero, indicating that there is permanent deformation, which is expected. However, upon reloading, each load cell quickly returns to the initial loading curve, and continues along the same path as initial loading.




Figure 4-7 Load Cell Reaction Versus Load

The forces in the load cells are much higher in the 36 ft span bridge unit compared to the 20 ft span bridge unit. This is due to the slightly angled legs. Therefore, a higher portion of the horizontal reaction goes into the load cells. Another possible reason for the increase in load cell forces is the relative stiffness of the 36 ft arch compared to the 20 ft arch. The 36 ft arch allowed for much greater rotation of the corners, which would increase the amount of lateral force at the base of the bridge unit.

Figure 4-8 shows the individual wirepot displacements during the ultimate load test. Note that, due to the preliminary loading portion of the test, there are loading, unloading, and reloading portions of the graph. The unloading curve for each wirepot does not return to zero, indicating that there is permanent deformation, which is expected. However, upon reloading, each wirepot quickly returns to the initial loading curve, and continues along the same path as initial loading.

With 5.96 in of vertical deflection at failure, the bridge was fairly flexible. This ultimate load deflection translates to roughly $L/70$. However, due to the relatively short legs, the unrestrained lateral deflections of the bridge walls were relatively small, maximum being 0.93 in at WP 3. Due to these small deflections, passive forces in the backfill soil would not mobilize. Therefore, for the 36 ft span, backfill soil would not significantly aid the ultimate strength of the bridge with its current leg height.




Figure 4-8 Deflection Versus Load

4.5 Observed Bridge Behavior and Failure

Due to issues shipping and handling the much larger and less stiff 36 ft span bridge unit, some cracking and spalling of the bridge occurred before testing. During the process of getting the bridge into the lab and onto the baseplates, initial flexural cracks formed at midspan and near the corners, but were still small prior to testing. More significantly, the bridge legs were placed on the baseplates such that they were not completely vertical, but slightly angled outward. This misalignment caused some spalling on the inside of the leg prior to testing, as can be seen in Figure 4-9. This misalignment also caused further spalling to occur during the test as more weight was placed on the bridge. The spalling and initial cracking did not affect the ultimate strength of the bridge, however.

The first significant cracks occurred at midspan, followed by cracks developing near the corners. Several cracks formed near midspan, approximately spaced evenly at six inches. These cracks propagated up through the thickness of the bridge well past midheight before failure. An image illustrating the even spacing of the cracks near midspan is included as Figure 4-10. The cracks near the corners were also approximately evenly spaced at six inches. These cracks widened and extended until failure, indicating some yielding of the steel reinforcement.



Figure 4-9 Initial Spalling on Bridge Leg



Figure 4-10 Midspan Cracking – 120 kips Total Load

The 36 ft span failed under a total applied load of 151.9 kips. The failure mechanism was flexural in nature, with a crack near the corner of the arch widening until the tension steel

ruptured, which quickly caused the concrete to crush in compression. The remaining uncrushed concrete and compression steel allowed the bridge to continue carrying some load, but rupture of the tension steel meant that further loading of the bridge would be futile. An image of the failure mechanism immediately before and after failure can be seen in Figures 4-11 and 4-12, respectively. The failure occurs between cross sections five and six, on the side of the bridge with wirepot three and load cells three and four. The ultimate load configuration can be seen in Figure 4-13.



Figure 4-11 Bridge Cracking Immediately Prior to Failure



Figure 4-12 Bridge Section Immediately After Failure




Figure 4-13 Failure Load Configuration

The flexural failure mechanism of the bridge was expected to occur near the corners. The failure mechanism was ductile and developed more slowly. The entire arch deformed considerably prior to the failure mechanism. The bridge could still carry some weight after failure, but would not have been able to hold nearly as much. The only surprise was the rupture of the tension steel prior to the crushing of the concrete.

It was noted that the failure mechanism passed through the location of the cast in place lifters used to lift the units during transportation. An image showing the failure surface passing through the lifter location can be seen in Figure 4-14. During production of this unit, the reinforcement is cut at lifter locations in order to place the lifters. This removed four bars from each mat, which translates to a loss of 17% of the reinforcement at that location for this particular bridge unit. This significantly weakened the ultimate load capacity of the cross section at the lifters, forcing the failure mechanism to occur at that spot. In order to prevent weakening of the structure, replacement reinforcement bars should be properly spliced to the reinforcing mats at lifter locations to prevent a loss of effective steel area.

The 36 ft span bridge unit was much more flexible than the 20 ft span bridge unit. This is due to the lower concrete strength, the larger clear span, and the fact that the 20 ft unit was designed for five more feet of backfill. As such, the 36 ft bridge unit held less load, developed higher moments, deflected significantly more in the arch section, and had significantly more cracking prior to failure. The 20 ft bridge unit did develop higher moments in the legs, due to the 20 ft span having a higher arch stiffness to leg stiffness ratio than the 36 ft span. The failure mechanism of the 36 ft bridge is much more ductile, and therefore more desirable.




Figure 4-14 Failure Through Lifter Location

4.6 Chapter Summary

The 36 ft bridge unit appeared to have sufficient strength, and was more ductile. Initial flexural cracking occurred in the high moment areas during transportation and handling. However, unlike the 20 ft span bridge unit, flexural cracks propagated, widened, and increased in number with a fairly uniform spacing underneath midspan and on top near the corners. The bridge unit held 151.9 kips of force before failure. Immediately prior to failure, maximum deflections were 5.96 in downward at midspan, and 0.93 in laterally in the walls. The failure mechanism was a flexural failure near one of the corners. The tension steel ruptured, quickly causing the concrete to crush in compression.

Chapter 5

Computer Modeling

5.1 Introduction

The objective in creating a structural computer model was to correlate the results of the model to those found during the laboratory testing. The computer software program used for development of the structural model was SAP2000. Since the structure was loaded to failure during the laboratory tests, the model was required to simulate the linear and nonlinear behavior of the arch. Therefore, the nonlinear capabilities of SAP2000 were of particular importance. SAP2000 was chosen in place of other programs that offered more soil-structure interaction capabilities due to the fact that the lab and field tests showed that the lateral restraint had minimal effect. SAP2000's ability to model reinforced concrete was easier to implement and researchers on the project had previous experience.

5.2 Model Development

Geometric dimensions based on the construction documents and physical measurements provided a reference point for which to construct the structural model. A barrel shell element with the appropriate length, roll down angle, radius, axial divisions, and angular divisions was created. Once the basic arch shape was created, the legs of the arch were manually drawn.

Using the concrete frame section generator within SAP2000, the cross sectional dimensions and reinforcing details were assigned to the frame elements. While a majority of the frame element could appropriately be assigned as uniform prismatic rectangular sections, the corner sections of the structure were in reality much stiffer due to a non uniform section. To represent this in the model, non-prismatic frame sections were assigned to these corner elements. The geometric properties of these elements linearly change throughout their length to two distinctly defined cross sections assigned at each end of the element. The prismatic and non-prismatic sections used in the 20 ft and 36ft clear span models are conceptually shown in Figures 5-1 and 5-2, respectively.




Figure 5-1 20 ft Clear Span – SAP2000 Elements




Figure 5-2 36 ft Clear Span – SAP2000 Elements

The material properties used in the SAP2000 model were a combination of default material properties built into the software and appropriate adjustments to these default properties based on tests performed using material samples taken from the structures tested. Concrete modulus of elasticity and compressive strength values used were those reported previously for the two arches tested in the Auburn University laboratory. The expected yield strength and ultimate strength of the reinforcing bars determined from the 36' span specimen were used in the models.

5.3 Nonlinear Analysis

To simulate the behavior observed in the laboratory testing in the SAP2000 model, the loading configuration was setup to be the same. Therefore, the point loading configuration used in the SAP2000 structural computer model matched that of the laboratory testing load setup.

Three point loads on the 20 ft and 36 ft clear span SAP2000 structural models were set at the locations used in the laboratory tests. The load cases incrementally increased the magnitude of each of these three point loads by 10 kips, a 30 kip total increase per load case. The lowest magnitude load case in both models was 20 kips per point load, 60 kips total load. The highest

magnitude load case for the 20 ft clear span model was 64 kips per point load, 192 kips total load. The highest magnitude load case in the 36 ft model was 51 kips per point load, 153 kips total load. As the laboratory testing carried out loading up to ultimate capacity of the structure, it was necessary to include nonlinear effects in the computer analysis model. This was accomplished in SAP2000 through the use of M3 hinges assigned to various frame elements throughout the structure in conjunction with nonlinear load cases.

User defined M3 type hinges were decided upon after considering the benefits and data comparison of various models with different types of hinges. M3 hinges are dependent on moments at the assigned hinge location. User defined M3 hinges accounted for these forces well and produced results with the best correlation those of the actual results in the laboratory. As the cross sectional properties of the structures were known from the construction documents, reinforcing detail specifications, and physical measurements taken in the laboratory, it was possible to perform detailed cross sectional analysis calculations for critical cross sections to define the needed range of data points necessary to utilize user defined M3 hinge properties.

The location of the hinges in the SAP2000 model matched the highest concentration of observed cracking and rotation during the laboratory testing of both the 20 ft clear span and 36 ft clear span structures. The location of the hinges in the 20 ft clear span and the 36 ft clear span SAP2000 structural model were (a) the corners of the structure, (b) approximately quarter span of the structure, and (c) midspan of the structure. The hinges and their locations in the 20 ft clear span model and the 36 ft clear span model are shown in Figures 5-3 and Figure 5-4, respectively.




Figure 5-3 Hinge Locations and Labels – 20 ft Clear Span Model




Figure 5-4 Hinge Locations and Labels – 36 ft Clear Span Model

Failure modes are not predicted by SAP2000. However, the “failure point” of the structure was assumed to have occurred when a drastic, unrealistic increase in deflection occurred in the model analysis. For the 20 ft clear span model, this drastic increase in displacement occurred around 65 kips per loading location, 195 kips total load. This was very close to the ultimate total load from testing, 184 kips. The deflection in the 20 ft clear span SAP2000 model increased from 1.839 in. at midspan with 192 kips total load to thousands of inches at midspan with 195 kips total load. The ultimate load capacity of the structure could be reasonably predicted based on the comparison of the 20 ft model capacity to laboratory specimen capacity.

For the 36 ft clear span model, the drastic increase in displacement occurred at approximately 52 kips per loading location, or a total load of 156 kips. This was very close to the ultimate total load in testing of the 36 ft clear span of approximately 152 kips. The deflection in the 36 ft clear span SAP2000 model drastically increased from 3.501 in. at a total load of 152 kips to thousands of inches around a total load of 156 kips. The ultimate load capacity of the structure was reasonably predicted based on a comparison of the 36 ft model capacity to the laboratory specimen capacity.

As is true of most concrete structures, loading resulted in flexural cracking of the concrete. Cracked sections have a decreased moment of inertia which directly decreases the stiffness of the overall structure. Prior to this cracking, the moment of inertia of a given cross section is often represented simply by the gross moment of inertia of the section. However, after cracking has occurred, it becomes necessary to adjust the moment of inertia to an effective moment of inertia for cross sectional analysis purposes since part of the section is cracked and therefore not contributing to the stiffness of the section. This was accounted for in the SAP2000 model to better represent the displacements of the midspan and the top of the walls.

5.4 Model Analysis Results

The objective of developing a SAP2000 structural model was to correlate the results of the model with those of the laboratory testing. The primary means of comparison used to evaluate

how well the model correlated to the laboratory results and to further develop the model were moment diagrams and deflections. Not all the results are shown in this report, for a more detailed presentation of the comparison of the model and the experimental tests see (Jensen, 2012).

The moment diagrams and displacements were found for each load case of the 20 ft clear span model and the 36 ft clear span model in order to compare the results to those recorded during the laboratory testing. Figure 5-5 shows a plot of the midspan moment versus the total load for the 20 ft clear span SAP2000 model compared to the midspan moment versus the total load for the 20 ft clear span test specimen. Figure 5-6 shows a plot of the midspan vertical deflection versus total load for the 20 ft clear span SAP2000 model compared to midspan deflection measured during the laboratory testing of the 20 ft clear span test specimen. Figure 5-7 shows a plot of the lateral deflections at the corners of the arch versus total load for the SAP2000 model analysis compared to the laboratory testing of the 20 ft clear span.

The midspan moment versus total load plot for the 20 ft clear span SAP2000 model has less than 20 percent difference than the laboratory throughout the range of loading. The SAP2000 model midspan moment was slightly lower than the 20 ft clear span laboratory test midspan moment throughout the range of testing.




Figure 5-5 Model Versus Laboratory Specimen – 20 ft Span Midspan Moment

The midspan displacement versus total load plot for the 20 ft clear span SAP2000 model is approximately 10 percent lower than the laboratory throughout the range of loading. The model midspan displacement was slightly lower than the 20 ft clear span laboratory test displacement throughout the range of testing. The corner displacement of the 20 ft clear span test specimen was slightly different for the two corners. The 20 ft clear span SAP2000 model was approximately 20 to 30 percent lower than the laboratory test specimen corner deflection.




Figure 5-6 Model Versus Laboratory Specimen – 20 ft Span Midspan Displacement




Figure 5-7 Model Versus Laboratory Specimen – 20 ft Span Corner Displacement

Figure 5-8 shows a plot of the midspan moment versus total load for the 36 ft clear span SAP2000 model compared to the midspan moment versus total load for the test specimen. Figure 5-9 shows a plot of the midspan vertical deflection versus total load for the 36 ft clear span SAP2000 model compared to midspan deflection measured during the laboratory testing of the 36 ft clear span test specimen. Figure 5-10 shows a plot of the quarter span moment versus total load for the 36 ft clear span SAP2000 model compared to the quarter span moment measured during testing of the 36 ft clear span test specimen.

The midspan moment generated by the 36 ft clear span SAP2000 model was less than 5 percent different than the laboratory specimen data throughout the first 40 percent of the load range. After the first 40 percent of the load range, the 36 ft clear span SAP2000 model gradually increased in its underestimate of the midspan moment. At the ultimate load the 36 ft clear span SAP2000 model was approximately 40 percent less than the midspan moment of the 36 ft clear span test specimen. The average difference between the SAP2000 model and the laboratory test specimen was approximately 25 percent.




Figure 5-8 Model Versus Laboratory Specimen – 36 ft Span Midspan Moment




Figure 5-9 Model Versus Laboratory Specimen – 36 ft Span Midspan Displacement




Figure 5-10 Model Versus Laboratory Specimen – 36 ft Span Corner Moment

The midspan displacement generated by the 36 ft clear span SAP2000 model was approximately 5 percent different than the laboratory specimen data throughout the first 70 percent of the load range. For the final 30 percent of the load range, the 36 ft clear span SAP2000 model gradually increased its underestimate of the midspan displacement. At the

ultimate load the 36 ft clear span SAP2000 model was approximately 30 percent less than the laboratory test specimen midspan displacement. The average difference between the 36 ft clear span SAP2000 model and 36 ft clear span laboratory test specimen for the final 30 percent of the load range was approximately 15 percent.

The two corner at arch moments measured in on the 36 ft clear span test specimen were different by approximately 30 to 40 percent. The corner arch moment generated in the 36 ft clear SAP2000 model fell, in between the two different corner at arch moments measured in the laboratory. Therefore, the SAP2000 model was approximately equal to the average of the two laboratory measured corner at arch moments throughout the load range.

5.5 Chapter Summary

The SAP2000 structural models provided good correlation of the moments and deflections seen during the laboratory testing. This was especially true throughout the first three quarters of the loading range. Near the ultimate capacity of the arches, the model underpredicted, with the exception of the model overpredicting the corner moment of the 20 ft clear span arch, the moments and deflection by 15 to 20 percent. Based on the results, the SAP2000 structural models provided a reasonable starting point for assessment of the design and performance of the arches which will be discussed in the following chapter.

Chapter 6

Design Methodology

6.1 Introduction

Foley Products provided the design calculations generated by the engineer of record for the bridges tested in the laboratory to evaluate the effectiveness of the arch structure design. The designs were evaluated based upon laboratory testing and the detailed SAP2000 model.

The same methodology was used in design of both the 20 ft clear span structure and the 36 ft clear span structure. The computer program RISA 3-D (RISA Technologies) was used to evaluate various load combinations. The RISA model analysis indicated the highest moment in the structure was at midspan. In the design calculations provided, this midspan moment was used to perform standard reinforced concrete design to specify the required reinforcing.

The effectiveness of the design methodology is discussed in this chapter. Details of the design methodology are provided. The RISA model used in design is compared to the SAP2000 model that correlated to laboratory results. An overall evaluation of the design is provided based on a comparison to laboratory testing and the corresponding SAP model. The ratio of demand to capacity at specific arch sections, namely midspan, was used to determine the effectiveness of the design.

6.2 Modeling and Analysis

The expected loads on the structure were calculated to begin design. The dead load was a function of the anticipated depth of fill. Live loads were calculated based on the 17th Edition of the American Association of State Highway and Transportation Officials Standard Specification for Highway Bridges HS20 design truck (AASHTO) (AASHTO, 2002). Allowance was made for impact loading as well as its distribution through a given depth of soil medium based on AASHTO provisions. Lateral loads, or pressures, were calculated based on the depth of fill above the point of interest. The vertical walls of the structure were the main location of interest in calculating the lateral soil pressure. This lateral pressure was calculated based on the unit weight of the soil being approximated at 120 pcf. The lateral pressure is based on the active case with a coefficient of lateral earth pressure equal to 0.3.

The analysis program RISA was used to create a structural model to determine the demand forces. The gravity and lateral loads were incorporated in the model. The controlling moment from the load cases, including load factors, considered in RISA was used to perform cross sectional

analysis in designing the section. Details of the RISA model and cross sectional analysis are discussed in a later section.

The RISA structural model used in the design of the Foley Arch was a two dimensional model that was based on common assumptions and practice in structural engineering. The 20 ft clear span RISA model was composed of 34 frame elements. All these elements were rectangular, prismatic frame elements. The concrete material defined in the 20 ft clear span RISA model was 5000 psi compressive strength. The reinforcing steel yield strength was 60 ksi. Support conditions in the model consisted of pin supports, no moment resistance, at the base of the vertical legs. The extruded view of the members is shown in Figure 6-1. The moment diagram from the RISA analysis is shown in Figure 6-2.




Figure 6-1 Extruded View – 20 ft Span RISA Model




Figure 6-2 Moment Diagram – 20 ft Span RISA Model

The maximum moment used in the cross sectional analysis and design provided was taken at midspan of the structure in Figure 6-2. The moment at this location in the 20 ft span location is 65

k-ft per foot of arch width. All calculations related to reinforced concrete design were in accordance with Section 8.16 of the 17th Edition AASHTO Standard Specification for Highway Bridges provisions. Based on the demand of 65 kip-ft, the required area of steel for a representative 1 ft wide strip was calculated to achieve the needed capacity. The design calculations were performed for a 1 ft width strip and therefore, to make comparisons with the test structures, they were multiplied by 4 since the bridge tested in the laboratory and modeled in SAP2000 was a 4 ft wide section.

Similar properties and methodology were used in the design of the 36 ft clear span structure. A two dimensional RISA structural model was developed for design purposes. The 36 ft clear span structure RISA model was composed of 42 frame elements. All these elements were rectangular prismatic frame elements. The concrete material defined in the 36 ft clear span RISA model was 6000 psi compressive strength. The reinforcing steel yield strength was 60 ksi. A view of the 36 ft span members and the schematic division of beam elements is shown in Figure 6-3. The moment diagram shown in Figure 6-4 is for the controlling factored load combination; this moment diagram was generated within RISA after having run the analysis.




Figure 6-3 Beam Elements – 36 ft Span RISA Model




Figure 6-4 Moment Diagram – 36 ft Span RISA Model

The maximum moment used in the cross sectional analysis and design provided was taken at midspan. The moment at this location in the 36 ft RISA model is 48.7 k-ft per foot of arch width. As was the case with the 20 ft clear span design calculations, all calculations for the 36 ft clear span related to reinforced concrete design were in accordance with the AASHTO Standard Specification. Based on the demand, the required area of steel for a representative 1 ft wide strip

was calculated. The design calculations were performed for a 1 ft width strip and therefore, to make comparisons with the test structures, they were multiplied by 4.

The design calculations were used to collect and record various properties of the Foley Arch as it was designed and modeled in RISA. The required flexural steel area at the midspan cross section was examined; the amount provided in construction of the structure fluctuated slightly with the steel area of actual reinforcing bars. The standard concrete and reinforcing bar yield strength were used to calculate the nominal flexural moment capacity of the cross section under consideration. These properties are shown in Table 6-1 and are from the design calculations provided by Foley Arch.

Table 6-1: Design Calculation Properties

Structure Clear Span	Design Calculations					Equivalent 4 ft Width Nominal Moment Capacity, M_n (k-ft)
	1 ft Width Flexural Steel Area, A_s (in ²)	Equivalent 4 ft Width Steel Area, A_s (in ²)	Compressive Strength, f'_c (psi)	Steel Yield Strength, f_y (ksi)	1 ft Width Nominal Moment Capacity, M_n (k-ft)	
20 ft	2.40	9.6	6,000	60	76.7	307
36 ft	1.22	4.88	6,000	60	54.4	218

The design moment capacity for the midspan section of the 20 ft clear span structure was 307 k-ft. The design moment capacity for the midspan section of the 36 ft clear span structure was 218 k-ft. One of the reasons for the high design moment capacity of the 20 ft clear span structure is the fact that it was designed for 10 ft of fill. The 36 ft clear span structure was designed for half the fill of the 20 ft structure, 5 ft. Depending on the depth of fill, the dead load is often the largest contributing factor. In the two structures under consideration herein, the design loads due to the soil fill were substantially greater than the AASHTO specified live loads.

A comparison between the RISA models and the SAP2000 models was made. The factored design loads put on the structure in the RISA model were for a 1 ft wide strip. Since the test structures were 4 ft wide, the factored loads from the RISA models were multiplied by 4. The resulting moment diagram for the factored loads on the 20 ft clear span in SAP2000 is shown in Figure 6-5 which is symmetric about midspan.




Figure 6-5 Moment Diagram of Factored Design Loads - 20 ft SAP2000 Model

The moment at midspan of the SAP2000 model under the factored design loads was approximately 90 k-ft. The moment at the corners of the arch of the SAP2000 model under the factored design loads was approximately 222 k-ft.

The resulting moment diagram for this load case on the 36 ft clear span in SAP2000 is shown in Figure 6-6 which is also symmetric about the midspan. The moment at midspan of the 36 ft SAP2000 model under the factored design loads was approximately 130 k-ft. The moment at the corners of the 36 ft SAP2000 model under the factored design loads was approximately 312 k-ft.




Figure 6-6 Moment Diagram of Factored Design Loads - 36 ft SAP2000 Model

A comparison was made between the moment diagrams output by RISA and by SAP2000 with the same design loading configuration applied. The moment diagram of the RISA model of the 20 ft clear span with the factored design loads applied was shown in Figure 6-2. This can be compared to the moment diagram of the SAP2000 model of the 20 ft clear span with the factored design loads applied in Figure 6-5. The moment diagram of the RISA model of the 36 ft clear span with the factored design loads applied was shown in Figure 6-4. This can be compared to the moment diagram of the SAP2000 model of the 36 ft clear span with the factored design loads applied in Figure 6-6. A summary of the comparison between moment magnitudes of the RISA model to the moment magnitudes of the SAP2000 models is shown in Table 6-2.

Table 6-2: Comparison of RISA and SAP2000 Model Moments

Location	RISA Model – Equivalent 4 ft Wide Section		SAP2000 Model	
	20 ft Clear Span Moment (k-ft)	36 ft Clear Span Moment (k-ft)	20 ft Clear Span Moment (k-ft)	36 ft Clear Span Moment (k-ft)
Midspan	260	196	90	130
Corner	68	130	222	312

The moments from the RISA model and the SAP2000 model do not correlate well. In the RISA model the midspan moment was the maximum. However, in the SAP2000 model the corner moments were the maximum. One reason this could be the case is that the corner section members in the SAP2000 model are deeper than those in the RISA model, therefore increasing the stiffness and moment flow to those areas. The SAP2000 model made use of non prismatic elements at the corner sections while the RISA model used prismatic elements assigned along a slightly different centerline. Both nonlinear and linear analyses were performed in SAP2000. Under the design loads being considered, the moment diagrams in both the linear and nonlinear case were the same magnitude. This indicates that nonlinear effects did not have a significant impact in the distribution of moments throughout the range of design loading.

Another possible source of difference is the incorporation of lateral springs in the RISA 3-D models. The effect of the springs representing the resistance of soil along the vertical legs of the RISA model have been added to account for additional soil pressure due to lateral deflection of the legs. The results of the spring forces in the RISA models are reasonable based on the experimental and analytical results with one exception. This exception is the spring at the bottom of the bridge. Based on the boundary conditions in the field, the assumption was made that the bottom of the bridge would act as a pin support. This was verified by the field serviceability test where the additional pressure due to the loading was very small at the base of the wall indicating a lack of outward deflection at the base of the wall. The RISA results for both bridges show displacements at the bottom of the bridge. If these supports were changed to a pin support, the

moments at the corners would increase and correlation with the SAP models and expected behavior would improve.

6.3 Experimental Results Versus Design

Midspan analysis was the only cross sectional analysis provided in the design calculations and will be used for comparing the laboratory testing and SAP2000 model. This comparison provides a means of evaluating the overall effectiveness of the design methodology currently used for the Foley Arch.

Table 6-3 shows the properties for the specimens tested in the laboratory. It shows the cross sectional flexural steel area in the lab specimens, the compressive strength of the concrete specimen samples, and the yield strength of the flexural steel used in the 20 ft clear span structure and the 36 ft clear span structures tested in the laboratory and modeled in SAP2000. Of particular interest from Table 6-3, is the compressive strength of the concrete in the 20 ft clear span test specimen. It was significantly higher than the design strength of 6000 psi. This may raise some concerns related to directly comparing the design calculations and associated moment capacity to the test specimens and corresponding SAP2000 model results.

Table 6-3: Test Structure Midspan Properties

Structure Clear Span	Test/Model Structure			
	Flexural Steel, A_s (in ²)	Compressive Strength, f'_c (psi)	Steel Yield Strength, f_y (ksi)	Ultimate Midspan Moment Capacity, M_u (kip-ft)
20 ft	8.02	12,506	65	448
36 ft	5.34	7,044	65	550

A comparison between the structure as it was designed and analyzed in RISA to the structure tested in the laboratory and the SAP2000 model was of primary interest at this stage of the project. The midspan cross sectional properties and capacity were at the critical location shown in the design calculations provided. For comparison, a ratio of test properties to design properties was used as shown in Table 6-4. The test properties used in the ratio is from the laboratory test specimen. The design properties are based on the details contained in the design calculations.

Table 6-4: Ratio of Design to Test/Model Specimen Properties

Structure Clear Span	$\frac{A_{s,Test}}{A_{s,Design}}$	$\frac{f'_{c,Test}}{f'_{c,Design}}$	$\frac{f_{y,Test}}{f_{y,Design}}$	$\frac{M_{u,Test}}{M_{u,Design}}$
20 ft	0.84	2.08	1.08	1.46
36 ft	1.09	1.17	1.08	2.52

The 20ft clear span structure and the 36ft clear span structure exceeded the required design strength. The structures are safe as designed under the test conditions. It appears that the 20 ft clear span test specimen had slightly less steel than called for in the reinforcement details in the design calculations. At the time of testing the 20 ft clear span concrete had reached a much higher compressive strength than was designed for. The effect of the small reduction in cross sectional steel and the significant difference in compressive strength on the structure was explored using the 20 ft clear span SAP2000 structural model. It was found that the difference in ultimate capacity was small enough that it could be neglected for the purpose of evaluating the design methodology. Based on the ratio of an average between the laboratory test and the model results to the design calculations, the 20ft clear span specimen had a 30 percent higher moment capacity at midspan than the design calculations for the same structure indicated. Based on the ratio of an average between the laboratory test and the model results to the design calculations, the 36ft clear span specimen had an 84 percent higher moment capacity at midspan than the design calculations. Both designs, the 20 ft clear span and 36 ft clear span, were reasonably effective. The 36 ft clear span is slightly higher than an ideal overstrength, but not to an exorbitant or overly uneconomical point.

6.4 Chapter Summary

It was concluded from evaluation of the 20 ft clear span structure and the 36 ft clear span structure that the designs were effective and the design methodology was reasonably well representative of actual behavior of the structure when tested with the exception of the spring support rather than the pin at the base. The designs are safe but not exceedingly overdesigned. It was also concluded that the SAP200 models and the RISA models did not have the same maximum moment locations under the factored design loads in the design calculations provided by Foley due to a combination of thicker corner sections in the SAP2000 models as well as springs incorporated into the RISA model, primarily the spring at the wall base, that were not in the SAP2000 models. While there were slight differences in the RISA and SAP2000 models when analyzed under approximately equivalent loads, this did not impact the determination of the overall capacity of the structure. It was concluded that the way the design methodology is carried out is safe and effective but the boundary conditions at the base should be modified to more closely represent in-situ behavior.

Chapter 7

SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

7.1 Summary

The use of precast, three-sided arch culverts has become fairly popular for new bridges and bridge replacements, but little research has been performed into the strength of these structures. Many have speculated that, due to arching action, significant lateral earth pressures can be developed in the backfill behind the legs. These pressures allow the bridge to achieve strengths larger than possible without the confinement of the backfill soil. The research in this report was performed to verify the behavior of these arch culverts through field testing of an existing bridge, as well as two ultimate load tests on bridge units.

It was discovered that, while the test bridges were capable of achieving very high strengths, they were too stiff to cause enough lateral deflection to activate passive earth pressures although the pressures developed does have a positive effect on performance. In addition, it was found that shear failures can occur in certain bridge designs, and the ductility of the steel used for reinforcement was not sufficient to allow flexural hinges to fully form.

Following the field and laboratory testing, computer models of the Foley Arch bridges were created in SAP2000 to correlate the results of the laboratory testing to the analysis and results of the computer model. This was used to determine if any economic or serviceability improvements could be reasonably recommended and/or implemented in the design or production of the structures.

7.2 Conclusions

Based on the field testing of a full 42 ft span bridge:

- The bridge had excellent service level behavior. While being subjected to two feet of backfill cover, as well as the load of a 56,820 lb truck, no cracking was observed in the structure and measured strains remained below the theoretical cracking strain.
- The largest lateral earth pressures were measured at the top of the side walls due to the arch thrusting outwards.
- Negligible lateral earth pressures were measured near the bottom of the side walls, indicating that the bridge supports act as a pinned connection.
- Lateral earth pressure magnitudes were relatively small and no passive earth pressures were mobilized in the backfill.
- Measurements during the backfill operation indicate no cracking in the structure, and that the presence of backfill causes a net compression throughout the bridge.

Based on the laboratory testing of a 20 ft span individual bridge unit:

- Due to their stiffness and strength, shorter spans designed for large amounts of fill could be subject to shear failures in the concrete.
- Due to stiffness in both the legs and the arch, measured lateral deflections were small, indicating that passive earth pressures would not be mobilized in the backfill soil.
- A critical area for failure is near the corners, where negative moment and shear are highest.

Based on the laboratory testing of a 36 ft span individual bridge unit:

- Longer spans behave much more flexibly, achieving much higher deflections before failure.
- Based on the observation that the tension steel ruptured prior to concrete crushing, ductility of steel reinforcement may not be high enough to fully develop hinges.
- Due to shortness of the legs, measured lateral deflections were small, indicating that passive earth pressures would not be mobilized in the backfill soil.
- A critical area for failure is in the negative moment regions near the corners of bridge units.
- For heavier, longer span, more flexible bridge units, additional care should be taken during shipping and placement to prevent premature cracking.
- Steel reinforcement removed to place the lifters should be replaced and adequately developed in order to prevent loss of strength.

Based on the computer modeling and evaluation of the design procedure:

- The data collected and analyzed provided a solid comparison point to move forward with the project in developing a structural computer model in SAP2000.
- The SAP2000 structural models provided good correlation of the moments and deflections seen during the laboratory testing. This was especially true throughout the first three quarters of the loading range.
- The designs were effective and the design methodology was reasonably well representative of actual behavior of the structure when tested.
- The only significant variation in design assumptions and expected behavior is a spring support at the base of the bridge legs. The design procedure should assume a pin support at the base of the legs.
- The designs are safe and not overly conservative.

7.3 Recommendations

The following recommendations for further research are recommended:

- Ultimate load testing of full sized bridges with backfill resistance

- Testing of longer span units with taller leg heights to research effect of lateral displacements and backfill pressure
- Comparison testing of similar units in both a laboratory and field setting

REFERENCES

- AASHTO (2002). "AASHTO Standard Specifications for Highway Bridges, 17th Edition. Washington, D.C.
- Foley Arch. (2010a). *Bridge No. 145 over Wiley Branch Creek on SR 1121 (Cabarrus Station Road)*. Calculations for Design of Precast Three Sided Arch Structure.
- Foley Arch. (2010b). *S.R. 54/Jonesboro Rd. Bike and Pedestrian Underpass*. Shop Drawings.
- Foley Arch. (2011). *Auburn Test Specimen 36' Span x 9' Tall with 5 Feet of Fill*. Calculations for Design of Precast Three Sided Arch Structure.
- Jensen, T.J. (2012). Numerically Modeling Structural Behavior of Precast Three Sided Arch Bridges for Design and Analysis. M.S. Thesis, Auburn University, May 2012.
- Meadows, R.L. (2012). Laboratory and Field Testing of Precast, Three Sided Arch Culverts. M.S. Thesis, Auburn, University, May 2012.
- RISA Technologies (2012). "RISA 3-D Rapid Interactive Structural Analysis – 3-Dimensional User's Guide. April 2012. <http://www.risatech.com/documents/risa-3d/R3DUsers.pdf>.
- SAP2000 (2010). SAP 2000 User's Manual. Berkeley, CA. Computers and Structures, Inc.